NOTE: If you are using a short window support bar or no support bar is required under the window then you must use DPC under the window sill. Option 1: It is acceptable to have both the DPC and support bar installed together.

Aluminium window frame (refer manufacturer for method of fixing & support)

MASONS Dryfix DPC

Continuous window support bar as required by window manufacturer

10mm min

MASONS PVC sill flashing. (Inside space to be filled with Plaster)

MASONS Barricade PLUS window tape

MASONS AAC render & coating system

Packers

Packer & Air Seal

5mm nominal

MASONS Barricade Building Wrap folded into opening & fixed to frame using appropriate fixings

MASONS Barricade Building Wrap

45x45 H3.2 AAC ENVIRO Ties

Note: MASONS Sill and base shoe flashings must be primed with Plasta Seal and coated with MASONS meshing render.

OPENING FLASHINGS
Window Sill with DPC Flashing
OPTION 1

Detail 60   Scale 1:2

MASONS ENVIRO AAC ON 45mm CAVITY TIMBER FRAME