



## PROFILED STEEL ROOF CLADDING - CLIPPED SYSTEM

Ventilated Ridge Barge Detail - Skillion Roof

Main contractor to ensure correct placement of purlins for fixing of Ridge Barge Vent

The Ridge/Barge flashing is to be supplied by the roof cladding supplier. Refer to E2/AS1 for minimum values of X & Z, recommend 200mm min at X to hide flashing tape

THIS IS A SUGGESTED METHOD OF VENTILATION BUT THE OVERALL DESIGN AND DIMENSIONS ARE THE RESPONSABILITY OF THE DESIGNER IN COMPLIANCE WITH THE NZ BUILDING CODE.

## Figure 09 Deep Trough Longrun - Skillion Roof Ridge Barge - RV10DT(half) + VB20 + VB10 Scale 1:5, 1:2

## Contact:

PH: 07 574 1116 EM: info@vent.nz

