

## TEST REPORT

for

**Speedfloor Ltd.**  
16B Ormiston Rd.  
Auckland, New Zealand 2016  
Hamish Coubray / 64 9 3034825

### Impact Sound Transmission Test

ASTM E 492 – 09 (2016)e1 / ASTM E 989 – 18

On

**Speedfloor 8" (200mm) Joist Floor-Ceiling Assembly  
Overlaid with 3-1/2 Inches (90mm) of Normal Weight Concrete,  
and 44 oz. Carpet and Foam Rubber Underlayment  
with 1.5"x2" Hat Channel, a Single Layer of 1/2 Inch Type C Gypsum Board**

Report Number: NGC 7020074\_R1

Assignment Number: G-1631

Test Date: 06/03/2020

Report Reissue Date: 10/02/2020

Submitted by:

  
Anthony J. Rivers  
Test Technician

Reviewed by:

  
Robert J. Menchetti  
Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

**Revision Summary:**

Date	SUMMARY
Approval Date: 07/23/2020	Original issue date: 07/23/2020 Original NGCTS report: NGC 7020074
Reissue Date: 10/02/2020	Report #: NGC 7020074_R1 The report was revised to fix a typographical error.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Report Number: NGC 7020074\_R1

Page 3 of 5

Test Method: This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine - Designation: E 492-09 (2016)e1 / E 989-18.

The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of ASTM E 492-09 (2016)e1.

Specimen Description: Speedfloor 8" (200mm) Joist floor-ceiling assembly overlaid with, according to client, 3-1/2 Inches (90mm) of Normal Weight concrete, 44 oz. Carpet over Foam Rubber Underlayment, 1.5" x 2" Hat Channel and a layer of 1/2" Type C gypsum board.

The test specimen was a floor assembly and was observed to consist of the following:  
All weights and dimension are averaged:

- 1 layer of 44 oz. Carpet. The carpet was floating on the Foam Rubber underlayment. Measured weight of 2.73 kg/m<sup>2</sup> (0.56 PSF).
- 1 layer of Foam Rubber Underlayment. The underlayment was floating on the Normal Weight concrete. The measured thickness of the underlayment was 9.65 mm (0.38 in.), Measured weight of 2.34 kg/m<sup>2</sup> (0.48 PSF).
- 1 layer of, 90mm (3-1/2 in.) Normal Weight concrete. Measured weight: 213.59 kg/m<sup>2</sup> (43.75 PSF)
- According to the client, Speedfloor 8" (200mm) joists. Measured weight: 6.01 kg/m<sup>2</sup> (1.23 PSF)
- 1.5" x 2 in. Hat Channel. The channel was spaced 406.4 mm (16 in.) o.c and was attached perpendicular to the joist. Measured weight of the channel: 0.82 kg/m<sup>2</sup> (0.17 PSF)
- 1 layer of 12.70 mm (1/2 in.) Type C gypsum board. The Gypsum board was attached to the Hat channel with 31.8 mm (1-1/4 in.) Type S screws spaced 203.2 mm (8 in.) o.c. Measured weigh: 9.28 kg/m<sup>2</sup> (1.90 PSF)

The overall weight of the test assembly is: 234.78 kg/m<sup>2</sup> (48.09 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough.

The test frame was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Conditioning: Minimum 24 hours at 70°F, 55% R.H

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Normalized impact sound pressure level						
Test: ASTM E 492 - 09 (2016) / ASTM E 989 - 18						
Test Report: NGC7020074_R1				Date: 6/3/2020		
Specimen Size [m <sup>2</sup> ]: 17.8				Page 4 of 5		
<b>Source room</b>			<b>Receiving room</b>			
Rm Temp [°C]: 25			Volume [m <sup>3</sup> ]: 124			
Humidity [%]: 50			Rm Temp [°C]: 25			
			Humidity [%]: 50			
<b>Impact Insulation Class IIC [dB]: 74</b>						
Sum of Unfavorable Deviations [dB]: 14						
Max. Unfavorable Deviation [dB]: 8			at 100 Hz			
Frequency	L <sub>n</sub>	L2	d	Corr.	u.Dev.	ΔL <sub>n</sub>
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
80	52	52.6	28.34	-0.6		1.46
100	46	46.3	29.71	-0.3	8	2.93
125	42	43.0	23.66	-1.0	4	1.08
160	40	42.0	17.79	-2.0	2	1.60
200	38	40.7	15.99	-2.7		0.84
250	29	32.4	15.32	-3.4		0.69
315	30	32.4	15.99	-2.4		0.55
400	32	34.0	17.68	-2.0		0.70
500	28	29.9	19.77	-1.9		0.59
630	24	26.1	20.56	-2.1		0.50
800	15	17.8	21.61	-2.8		0.45
1000	10	13.8	20.32	-3.8		0.49
1250	10	13.2	20.43	-3.2		0.32
1600	9	12.5	21.46	-3.5		0.63
2000	7	9.7	24.03	-2.7		0.46
2500	6	8.8	26.74	-2.8		0.49
3150	8	10.1	29.65	-2.1		0.59
4000	8	9.5	31.46	-1.5		0.40
5000	8	8.7	36.60	-0.7		0.27

L<sub>n</sub> = Normalized Sound Pressure Level, dB  
 L2 = Receiving Room Level, dB  
 d = Decay Rate, dB/second  
 ΔL<sub>n</sub> = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

**Normalized impact sound pressure level**


Test: ASTM E 492 - 09 (2016) / ASTM E 989 - 18

Page 5 of 5

Test Report: NGC7020074\_R1  
 Test Date: 6/3/2020  
 Specimen Size [m²]: 17.8

**Impact Insulation Class IIC [dB]: 74**

Frequency [Hz]	$L_n$ [dB]
80	52
100	46
125	42
160	40
200	38
250	29
315	30
400	32
500	28
630	24
800	15
1000	10 *
1250	10 *
1600	9 *
2000	7 *
2500	6 *
3150	8 *
4000	8 *
5000	8 *



\* Due to high insulating value of specimen, background levels limit results at these frequencies.

$L_n$  = Normalized Sound Pressure Level, dB

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.