

TEST REPORT

for

Speedfloor Ltd.
16B Ormiston Rd.
Auckland, New Zealand 2016
Hamish Coubray / 64 9 3034825

Sound Transmission Loss Test

ASTM E 90 – 09 (2016) / E 413 – 16

On

**Speedfloor 8" (200mm) Joist Floor-Ceiling Assembly
Overlaid with 3-1/2 Inches (90mm) of Normal Weight Concrete,
and 3/8" Engineered Wood Flooring over Stock Underlayment
with Furring Channel, a Single Layer of 1/2 Inch Type C Gypsum Board
and 3 Inches of Mineral Wool Insulation**

Report Number: NGC 5020072_R1

Assignment Number: G-1631

Test Date: 06/16/2020

Report Reissue Date: 10/05/2020

Submitted by:


Anthony J. Rivers
Test Technician

Reviewed by:


Robert J. Menchetti
Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Revision Summary:

| Date | SUMMARY |
|---------------------------|---|
| Approval Date: 07/24/2020 | Original issue date: 07/24/2020 Original NGCTS report: NGC 5020072 |
| Reissue Date: 10/05/2020 | Report #: NGC 5020072_R1 The report was revised to fix a typographical error. |

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Report Number: NGC 5020072_R1

Page 3 of 5

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

Specimen Description: Speedfloor 8" (200mm) Joist floor-ceiling assembly overlaid with, according to client, 3-1/2 Inches (90mm) of Normal Weight concrete, 3/8" Engineered Wood flooring over Stock Underlayment, Furring Channel and a layer of 1/2" Type C gypsum board, with 3 inches of Mineral wool insulation.

The test specimen was a floor assembly and was observed to consist of the following:
All weights and dimension are averaged:

- 1 layer of, 3/8" Engineered Wood flooring. The flooring was floating on the stock underlayment. Measured thickness: 9.65 mm (0.38 in.). Measured weight: 5.78 kg/m² (1.18 PSF)
- 1 layer of, stock underlayment. The underlayment was floating on the Normal Weight concrete. Measured thickness: 2.29 mm (0.09 in.). Measured weight: 0.78 kg/m² (0.16 PSF)
- 1 layer of, 90mm (3-1/2 in.) Normal Weight concrete. Measured weight: 213.59 kg/m² (43.75 PSF)
- According to the client, Speedfloor 8" (200mm) joists. Measured weight: 6.01 kg/m² (1.23 PSF)
- Furring. The channel was spaced 406.4 mm (16 in.) o.c and was attached perpendicular to the joist. Measured weight of the channel: 0.73 kg/m² (0.15 PSF)
- 1 layer of, 76.2 mm (3 in.) Mineral Wool insulation. Sample weight: 3.61 kg/m² (0.74 PSF)
- 1 layer of 12.70 mm (1/2 in.) Type C gypsum board. The Gypsum board was attached to the furring channel with 31.8 mm (1-1/4 in.) Type S screws spaced 203.2 mm (8 in.) o.c. Measured weigh: 9.28 kg/m² (1.90 PSF)

The overall weight of the test assembly is: 239.76 kg/m² (49.11 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough.

The test frame was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Conditioning: Minimum 24 hours at 70°F, 55% R.H

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

| Sound Transmission Loss Test Data | | | | | | | |
|---|----------|---------|---------|-------------------------------|------------|-----------------|------|
| Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16 | | | | | | | |
| Test Report: NGC 5020072_R1 | | | | | | Date: 6/16/2020 | |
| Specimen Size [m ²]: 17.8 | | | | | | Page 4 of 5 | |
| Source room | | | | Receiving room | | | |
| Volume [m ³]: 86 | | | | Volume [m ³]: 124 | | | |
| Rm Temp [°C]: 25 | | | | Rm Temp [°C]: 25 | | | |
| Humidity [%]: 50 | | | | Humidity [%]: 50 | | | |
| Sound Transmission Class STC [dB]: 57 | | | | | | | |
| Sum of Unfavorable Deviations [dB]: 26 | | | | | | | |
| Max. Unfavorable Deviation [dB]: 6 at 400 Hz | | | | | | | |
| Frequency [Hz] | STL [dB] | L1 [dB] | L2 [dB] | d [dB/s] | Corr. [dB] | u.Dev. [dB] | ΔSTL |
| 80 | 38 | 100.9 | 65.2 | 32.6 | 2.3 | | 2.20 |
| 100 | 41 | 103.2 | 65.2 | 30.3 | 3.0 | | 4.86 |
| 125 | 37 | 104.6 | 71.8 | 20.3 | 4.2 | 4 | 1.73 |
| 160 | 44 | 105.8 | 66.9 | 16.7 | 5.1 | | 1.61 |
| 200 | 44 | 104.9 | 66.4 | 15.4 | 5.4 | 3 | 0.68 |
| 250 | 47 | 102.8 | 61.6 | 15.5 | 5.8 | 3 | 1.27 |
| 315 | 48 | 100.5 | 57.3 | 16.5 | 4.8 | 5 | 0.52 |
| 400 | 50 | 99.4 | 54.0 | 17.7 | 4.6 | 6 | 0.90 |
| 500 | 53 | 99.0 | 50.9 | 19.2 | 4.9 | 4 | 0.71 |
| 630 | 57 | 100.4 | 47.9 | 20.2 | 4.5 | 1 | 1.33 |
| 800 | 59 | 99.0 | 43.7 | 20.7 | 3.7 | | 1.33 |
| 1000 | 62 | 96.7 | 38.6 | 19.6 | 3.9 | | 1.04 |
| 1250 | 67 | 95.4 | 33.0 | 20.0 | 4.6 | | 1.45 |
| 1600 | 68 | 96.4 | 32.2 | 21.4 | 3.8 | | 1.84 |
| 2000 | 68 | 98.7 | 34.2 | 24.5 | 3.5 | | 1.87 |
| 2500 | 71 | 100.4 | 32.1 | 27.4 | 2.7 | | 2.06 |
| 3150 | 69 | 99.7 | 32.7 | 30.7 | 2.1 | | 2.44 |
| 4000 | 68 | 97.3 | 31.6 | 32.9 | 2.2 | | 2.89 |
| 5000 | 66 | 90.7 | 26.5 | 37.2 | 1.7 | | 3.03 |

STL = Sound Transmission Loss, dB
 L1 = Source Room Level, dB
 L2 = Receiving Room Level, dB
 d = Decay Rate dB/second
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.


Sound Transmission Loss Test Data

Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16

Test Report: NGC 5020072_R1
 Test Date: 6/16/2020
 Specimen Size [m²]: 17.8

Sound Transmission Class STC = 57 dB

| Frequency [Hz] | STL [dB] | ΔSTL |
|-------------------|-------------|------|
| 80 | 38 | 2.20 |
| 100 | 41 | 4.86 |
| 125 | 37 | 1.73 |
| 160 | 44 | 1.61 |
| 200 | 44 | 0.68 |
| 250 | 47 | 1.27 |
| 315 | 48 | 0.52 |
| 400 | 50 | 0.90 |
| 500 | 53 | 0.71 |
| 630 | 57 | 1.33 |
| 800 | 59 | 1.33 |
| 1000 | 62 | 1.04 |
| 1250 | 67 | 1.45 |
| 1600 | 68 | 1.84 |
| 2000 | 68 | 1.87 |
| 2500 | 71 | 2.06 |
| 3150 | 69 | 2.44 |
| 4000 | 68 | 2.89 |
| 5000 | 66 | 3.03 |



* Due to high insulating value of specimen, background levels limit results at these frequencies.

STL = Sound Transmission Loss, dB
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.