

TEST REPORT

for

Speedfloor Ltd.
16B Ormiston Rd.
Auckland, New Zealand 2016
Hamish Coubray / 64 9 3034825

Sound Transmission Loss Test

ASTM E 90 – 09 (2016) / E 413 – 16

On

**Speedfloor 8" (200mm) Joist Floor-Ceiling Assembly
Overlaid with 3-1/2 Inches (90mm) of Normal Weight Concrete,
and 44 oz. Carpet and Foam Rubber Underlayment
with 1.5"x2" Hat Channel, a Single Layer of 1/2 Inch Type C Gypsum Board**

Report Number: NGC 5020063_R1

Assignment Number: G-1631

Test Date: 06/03/2020

Report Reissue Date: 10/05/2020

Submitted by:


Anthony J. Rivers
Test Technician

Reviewed by:


Robert J. Menchetti
Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Revision Summary:

Date	SUMMARY
Approval Date: 07/23/2020	Original issue date: 07/23/2020 Original NGCTS report: NGC 5020063
Reissue Date: 10/05/2020	Report #: NGC 5020063_R1 The report was revised to fix a typographical error.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Report Number: NGC 5020063_R1

Page 3 of 5

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

Specimen Description: Speedfloor 8" (200mm) Joist floor-ceiling assembly overlaid with, according to client, 3-1/2 Inches (90mm) of Normal Weight concrete, 44 oz. Carpet over Foam Rubber Underlayment, 1.5" x 2" Hat Channel and a layer of 1/2" Type C gypsum board.

The test specimen was a floor assembly and was observed to consist of the following:
All weights and dimension are averaged:

- 1 layer of 44 oz. Carpet. The carpet was floating on the Foam Rubber underlayment. Measured weight of 2.73 kg/m² (0.56 PSF).
- 1 layer of Foam Rubber Underlayment. The underlayment was floating on the Normal Weight concrete. The measured thickness of the underlayment was 9.65 mm (0.38 in.), Measured weight of 2.34 kg/m² (0.48 PSF).
- 1 layer of, 90mm (3-1/2 in.) Normal Weight concrete. Measured weight: 213.59 kg/m² (43.75 PSF)
- According to the client, Speedfloor 8" (200mm) joists. Measured weight: 6.01 kg/m² (1.23 PSF)
- 1.5" x 2 in. Hat Channel. The channel was spaced 406.4 mm (16 in.) o.c and was attached perpendicular to the joist. Measured weight of the channel: 0.82 kg/m² (0.17 PSF)
- 1 layer of 12.70 mm (1/2 in.) Type C gypsum board. The Gypsum board was attached to the Hat channel with 31.8 mm (1-1/4 in.) Type S screws spaced 203.2 mm (8 in.) o.c. Measured weigh: 9.28 kg/m² (1.90 PSF)

The overall weight of the test assembly is: 234.78 kg/m² (48.09 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough.

The test frame was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Conditioning: Minimum 24 hours at 70°F, 55% R.H

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Sound Transmission Loss Test Data							
Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16							
Test Report: NGC 5020063_R1				Date: 6/3/2020		Page 4 of 5	
Specimen Size [m²]: 17.8							
Source room				Receiving room			
Volume [m³]: 86				Volume [m³]: 124			
Rm Temp [°C]: 25				Rm Temp [°C]: 25			
Humidity [%]: 50				Humidity [%]: 50			
Sound Transmission Class STC [dB]: 57							
Sum of Unfavorable Deviations [dB]: 30							
Max. Unfavorable Deviation [dB]: 8				at 125 Hz			
Frequency	STL	L1	L2	d	Corr.	u.Dev.	ΔSTL
[Hz]	[dB]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
80	39	98.9	63.3	26.6	3.4		2.46
100	33	100.5	69.7	29.8	2.2		3.10
125	33	102.2	72.8	24.5	3.6	8	2.22
160	39	103.6	69.3	17.7	4.7	5	3.16
200	42	100.6	63.9	15.7	5.3	5	2.15
250	46	99.5	59.0	16.1	5.5	4	3.40
315	49	99.3	55.8	16.6	5.5	4	3.99
400	53	98.7	50.5	18.0	4.8	3	4.13
500	56	96.8	45.9	18.9	5.0	1	3.28
630	59	97.5	43.2	19.9	4.7		3.28
800	61	96.5	39.8	21.3	4.2		3.42
1000	62	92.1	34.7	20.0	4.6		3.19
1250	67	90.2	27.8	20.7	4.6		3.23
1600	71	91.0	24.5	21.1	4.4		4.06
2000	74	93.1	23.0	24.2	3.9		4.08
2500	74	94.5	23.6	26.8	3.2		4.15
3150	75	93.5	21.0	30.3	2.5		5.18
4000	76	91.1	17.3	32.9	2.2		4.81
5000	71	83.9	14.2	36.4	1.3		5.22
STL = Sound Transmission Loss, dB L1 = Source Room Level, dB L2 = Receiving Room Level, dB d = Decay Rate dB/second Δ STL = Uncertainty for 95% Confidence Level							

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

Sound Transmission Loss Test Data

Page 5 of 5

Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16

Test Report: NGC 5020063_R1


Test Date: 6/3/2020

Specimen Size [m²]: 17.8

Sound Transmission Class STC = 57 dB

Frequency [Hz]	STL [dB]	ΔSTL
80	39	2.46
100	33	3.10
125	33	2.22
160	39	3.16
200	42	2.15
250	46	3.40
315	49	3.99
400	53	4.13
500	56	3.28
630	59	3.28
800	61	3.42
1000	62	3.19
1250	67	3.23
1600	71	4.06
2000	74	4.08
2500	74	4.15
3150	75	5.18
4000	76	4.81
5000	71	5.22

* Due to high insulating value of specimen, background levels limit results at these frequencies.



STL = Sound Transmission Loss, dB
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.