

## TEST REPORT

for

**Speedfloor Ltd.**  
16B Ormiston Rd.  
Auckland, New Zealand 2016  
Hamish Coubray / 64 9 3034825

### Sound Transmission Loss Test

ASTM E 90 – 09 (2016) / E 413 – 16

On

**Speedfloor 8" (200mm) Joist Floor-Ceiling Assembly  
Overlaid with 3-1/2 Inches (90mm) of Normal Weight Concrete,  
and Porcelain Tile over 6mm AcustiCork Underlayment  
with 1.5"x2" Hat Channel, a Single Layer of 1/2 Inch Type C Gypsum Board**

Report Number: NGC 5020062\_R1

Assignment Number: G-1631

Test Date: 06/02/2020

Report Reissue Date: 10/05/2020

Submitted by:

  
Anthony J. Rivers  
Test Technician

Reviewed by:

  
Robert J. Menchetti  
Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

**Revision Summary:**

Date	SUMMARY
Approval Date: 07/23/2020	Original issue date: 07/23/2020 Original NGCTS report: NGC 5020062
Reissue Date: 10/05/2020	Report #: NGC 5020062_R1 The report was revised to fix a typographical error.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.

Report Number: NGC 5020062\_R1

Page 3 of 5

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

Specimen Description: Speedfloor 8" (200mm) Joist floor-ceiling assembly overlaid with, according to client, 3-1/2 Inches (90mm) of Normal Weight concrete, Porcelain Tile over 6mm AcoustiCork Underlayment, 1.5" x 2" Hat Channel and a layer of 1/2" Type C gypsum board.

The test specimen was a floor assembly and was observed to consist of the following:  
All weights and dimension are averaged:

- 1 layer of, Porcelain Tile. The tile was adhered to the 6mm AcoustiCork underlayment using thin set mortar, and grouted with Spectralock Pro Grout. Measured thickness: 8.89 mm (0.35 in.). Measured weight: 19.43 kg/m<sup>2</sup> (3.98 PSF)
- 1 layer of, 6mm AcoustiCork underlayment. The underlayment was adhered to the concrete slab using Mapei Ultrabond ECO350 adhesive. The adhesive was applied using a 0.06 mm x 0.06 mm x 0.03 mm (1/16 in. x 1/16 in. x 1/16 in.) Square-Notch Trowel. Measured thickness: 6.10 mm (0.24 in.). Measured weight: 1.17 kg/m<sup>2</sup> (0.24 PSF)
- 1 layer of, 90mm (3-1/2 in.) Normal Weight concrete. Measured weight: 213.59 kg/m<sup>2</sup> (43.75 PSF)
- According to the client, Speedfloor 8" (200mm) joists. Measured weight: 6.01 kg/m<sup>2</sup> (1.23 PSF)
- 1.5" x 2 in. Hat Channel. The channel was spaced 406.4 mm (16 in.) o.c and was attached perpendicular to the joist. Measured weight of the channel: 0.82 kg/m<sup>2</sup> (0.17 PSF)
- 1 layer of 12.70 mm (1/2 in.) Type C gypsum board. The Gypsum board was attached to the Hat channel with 31.8 mm (1-1/4 in.) Type S screws spaced 203.2 mm (8 in.) o.c. Measured weight: 9.28 kg/m<sup>2</sup> (1.90 PSF)

The overall weight of the test assembly is: 250.30 kg/m<sup>2</sup> (51.27 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough.

The test frame was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Conditioning: Minimum 24 hours at 70°F, 55% R.H

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agency of the Federal Government. This report may not be reproduced except in full, without written approval of the laboratory.


<b>Sound Transmission Loss Test Data</b>							
<b>Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16</b>							
Test Report: NGC 5020062_R1						Date: 6/2/2020	
Specimen Size [m <sup>2</sup> ]: 17.8						Page 4 of 5	
<b>Source room</b>				<b>Receiving room</b>			
Volume [m <sup>3</sup> ]: 86				Volume [m <sup>3</sup> ]: 124			
Rm Temp [°C]: 25				Rm Temp [°C]: 25			
Humidity [%]: 50				Humidity [%]: 50			
<b>Sound Transmission Class STC [dB]: 54</b>							
Sum of Unfavorable Deviations [dB]: 31							
Max. Unfavorable Deviation [dB]: 7 at 160 Hz							
Frequency [Hz]	STL [dB]	L1 [dB]	L2 [dB]	d [dB/s]	Corr. [dB]	u.Dev. [dB]	ΔSTL
80	42	103.2	64.3	29.3	3.1		3.70
100	34	103.7	72.9	28.1	3.3		4.49
125	32	103.7	76.0	21.4	4.3	6	1.87
160	34	102.6	73.6	18.0	5.0	7	1.36
200	42	104.9	68.5	15.3	5.7	2	0.88
250	44	101.2	62.7	15.8	5.5	3	1.28
315	45	100.7	60.8	16.3	5.1	5	0.27
400	47	98.8	57.1	17.7	5.3	6	0.57
500	52	100.0	52.6	19.1	4.6	2	0.66
630	55	101.3	50.6	20.5	4.3		0.50
800	59	100.4	45.8	21.4	4.4		0.61
1000	61	97.8	41.5	20.1	4.7		0.76
1250	66	95.8	34.5	20.4	4.7		0.62
1600	70	96.3	30.1	21.4	3.8		0.74
2000	73	98.5	29.0	24.4	3.5		0.96
2500	72	99.6	30.3	27.0	2.7		1.09
3150	75	99.4	26.9	30.0	2.5		1.49
4000	77	96.7	21.6	32.9	1.9		2.00
5000	80	90.0	11.8	36.2	1.8		2.05

STL = Sound Transmission Loss, dB  
 L1 = Source Room Level, dB  
 L2 = Receiving Room Level, dB  
 d = Decay Rate dB/second  
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

Sound Transmission Loss Test Data			Page 5 of 5
Test: ASTM E 90 - 09 (2016) / ASTM E 413 - 16			
Test Report: NGC 5020062_R1 Test Date: 6/2/2020 Specimen Size [m <sup>2</sup> ]: 17.8			
<b>Sound Transmission Class STC = 54 dB</b>			
<b>Frequency</b>	<b>STL</b>	<b>ΔSTL</b>	
[Hz]	[dB]		
80	42	3.70	
100	34	4.49	
125	32	1.87	
160	34	1.36	
200	42	0.88	
250	44	1.28	
315	45	0.27	
400	47	0.57	
500	52	0.66	
630	55	0.50	
800	59	0.61	
1000	61	0.76	
1250	66	0.62	
1600	70	0.74	
2000	73	0.96	
2500	72	1.09	
3150	75	1.49	
4000	77	2.00	
5000	80	2.05	

**STL vs. Frequency**



\* Due to high insulating value of specimen, background levels limit results at these frequencies.

STL = Sound Transmission Loss, dB  
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP, NIST or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.