

TEL: 09 579-8895 FAX: 09 579-2933

EMAIL: sales@nzfiredoors.co.nz

NZ Fire Doors Ltd, 89 Gavin Street, Ellerslie, PO Box 12709, Penrose 1642, Auckland, New Zealand. www.nzfiredoors.co.nz

# Data sheet



# E-90-H: Exterior 90 to 240 minute FRR hinged door, single or pair

- Our most popular 90, 120, 180 or 240 minute FRR hinged exterior fire, smoke and acoustic door set, the E-90-H is available in singles or pairs.
   The door leaf is a mineral core faced on all sides and edges with 1mm steel (E-CORE). The standard door set is supplied in plain galvanised or zincalume finish. Leaf sizes up to 2440 high x 1200 wide per leaf.
- Thickness 44 55 mm
- Weight 28.2 kg /m<sup>2</sup>
- Acoustic singles and doubles up to STC 35. Call us on 09 579-8895 for bespoke engineered solutions to higher STC ratings.

### **FACING OPTIONS**

- Paint quality galvanised or zincalume steel
- Powder coat finished (surcharge applies)

### **LEAF EDGE DETAILS**

• 39 x 12 integral rail (all edges) under folded steel capping


# PAIR MEETING STYLES Aluminium C/C C/J J/J F20 Seal (non active leaf) F20 Seal (non active leaf)

### **JAMB TYPES AND PROFILES**

1.6 mm electrogalv steel (types 5, 6, 7 & Speedwall), paint quality or powdercoat options available


### T5 – Steel

Steel width 111 - 350 mm




## T6 – Steel

Steel width 146 - 208mm




### T7 – two piece split steel

Ideal for retrofit situations. No additional charge. Min 104mm if masonary wall, Min 112mm if stud wall – no max..



### Steel Speedwall

Requires Speedwall C track (80mm end cap), (Max - /120/30sm)



### **SIDELIGHTS AND OVERLIGHTS**

Not available for 90+ minute FRR fire door sets

### **APPROVED HARDWARE**

The minimum requirement is for a fire door to be self-closing and self-latching. Hardware must be selected from NZ Fire Doors' Approved Hardware list from the column '90, 120 min'. Fitting any hardware that inhibits self-closing or self-latching is not approved by NZS 4520

IMPORTANT: Fitting untested or inappropriate hardware may affect the performance of the door and will void the warranty