



Steel Rollformed Products Ltd

27b Olive Rd Penrose
Ph. 5790175 Fax 5790174
Mob 0274719064 P.O Box 12172 Penrose
Email: srpltd@xtra.co.nz

Producer Warranty

This is to verify that the product manufactured by **Steel Rollformed Products Ltd** when used in normal dry conditions and installed as per **Steel Rollformed Products Ltd** installation manuals and span tables will have a minimum service lifespan of 15 years. Any out of scope work must be brought to the attention of **Steel Rollformed Products Ltd** and a Qualified registered engineer. Failure to do so will result in a void warranty.

The material used in the manufacture **Steel Rollformed Products Ltd** steel products is provided to us from **BHP New Zealand Steel**. The Zinc coating conforms to **2275 grams per square meter** as is standard for this application and attracts a 50-year warranty when stored and installed per the **New Zealand Steel** durability statement of **October 2008**. Please refer to the **New Zealand Steel** durability statement for clarification.

This is to certify that all wall and ceiling profiles manufactured by **Steel Rollformed products Ltd** are to international profiles, gauges ,steel strength, durability and accepted standards, in particular **ASNZ4600** (steel chemical composition, gauge grade tolerance, galvanised coating, testing statistics, yield point etc.

Wall and ceiling products manufactured by **Steel Rollformed Products Ltd** will not compromise structural integrity, acoustic or fire ratings.


This is to certify that **Steel Rollformed Products Ltd** wall and ceiling components adhere and conform to the following code requirements for manufacture and installation -

1. Z725 (galvanised coatings)
2. NZS4129 (seismic)
3. NZS3404 (fabrication)
4. AS1397 (sheet and strip)
5. AS1538 (cold rolled)
6. ASZNZ1170 (steel structures)

Performance, Storage and Handling.

This product will perform as specified, provided the fabrication and erection procedures are in accordance with standard and good trade practice.

It is preferable to maintain the bundles strapped as supplied to minimise damage. The bundles should be kept dry to minimise premature deterioration of the galvanised coating. It is recommended the wall structure is installed only after the building has been closed in. The Studs should be installed at centres and spans in accordance with the plasterboard manufacturer's recommendations.



Mark Bedford
Managing Director
Steel Rollformed Products Ltd