

Acoustical Testing Laboratory



TEST REPORT

for

DIV.TR.003

PROPERTY OF DIVERSIFIED INDUSTRIES

Not for Reproduction or Distribution

□ Released to Sales

☐ Internal Only

Diversified Foam Products 5117 Central Highway Pennsauken NJ 08109 Conrad Ambrette / 856-662-1981

Sound Transmission Loss Test ASTM E 90 - 02 On

Floor-Ceiling Assembly 6" Concrete Slab with Suspended Gypsum Ceiling Overlaid with; Wood Laminate Flooring over FloorMuffler Underlayment

Page 1 of 4

Test Numbers: NGC 5004002

Assignment Number: G-192

CONFIDENTIAL

Specimen Receipt Date: NA

Test Date: 02/25/2004

Not for release or reproduction

Report Date: 02/26/2004

Submitted by:

Craig G. Cooper

Test Engineen

Reviewed by:

Robert J. Menchett

Director

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.



1650 Military Road · Buffalo, NY 14217-1198 (716)873-9750 · Fax (716)873-9753 · ngctest@nationalgypsum.com



Acoustical Testing Laboratory

Page 2 of 4

Report Number: NGC 5004002

Test Method: This test method generally follows * the American Society for Testing and Materials

Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of

Building Partitions and Elements - Designation: E 90 - 02.

Specimen Description:

Floor-ceiling assembly. 6" concrete slab with suspended gypsum ceiling covered with, according to client; wood laminate flooring over FloorMuffler Underlayment.

The test specimen was a floor-ceiling assembly consisting of the following:

- 1 layer of T&G wood laminate flooring, 5/16" thick, 7-3/4" wide planks, (1.58 PSF).

- 1 layer of, green foam, 0.075" thick underlayment (0.022 PSF).

- 1 layer 6" reinforced concrete (75.0 PSF)

- Drywall grid suspension system consisting of 5/8" type X gypsum board (2.3 PSF) attached with 1-1/8" screws, 12" o.c. to suspended grid suspension system. 12" plenum with 3-1/2" lay-in fiberglass insulation (0.16 PSF).

The overall weight of the test assembly is 79.1 PSF nominal.

The perimeter of the floor assembly was sealed with rubber gasketing and a sand filled trough. The test assembly is structurally isolated from the receiving room. Board joints were taped and the ceiling perimeter was sealed with acoustical caulk.

Specimen size: 12 ft x 16 ft.

Test samples were submitted by client and tested as received.

Conditioning: NA

Test Results: The results of the tests are given on pages 3 and 4.

* Tests conducted in Floor-Ceiling chambers do not meet all requirements of the most recent ASTM E 90 Standard.

CONFIDENTIAL




Not for release or reproduction

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. This report may not be reproduced except in full, without the written approval of the laboratory. The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.





Acoustical Testing Laboratory





Not for release or reproduction

Sound Transmission Loss Test Data

Page 3 of 4

Per: ASTM E 90 - 02 / ASTM E 413 - 87

No. of test report: NGC5004002

Test Date: 2/25/2004

Size: 17.8 m²

Temperature [°C]: 19.8

Sound Transmission Class STC = 73 dB

Sum of unfavorable deviations: 30.0 dB

Max. unfavorable deviation: 7.0 dB at 125 Hz

Frequency	STL	L1	L2	T	Corr.	u.Dëv.	ΔSTL
[Hz]	[dB]	[dB]	[dB]	[s]	[dB]	[dB]	
100	51	103.9	60.4	2.15	7.7	÷	1.249
125	50	99.4	57.2	2.12	7.7	7.0	1.536
160	54	101.2	56.6	3.07	9.3	6.0	0.616
200	- 58	98.7	49.8	3.09	9.3	5.0	0.548
250	62	99.2	46.6	3.22	9.5	4.0	0.574
315	67	100.2	42.4	3.03	9.2	2.0	0.548
400	71	102.1	39.8	2.90	9.0	1.0	0.300
500	71	99.5	37.4	2.75	8.8	2.0	0.686
630	.71	98.1	35.6	2.66	8.7	3.0	0.400
800	.77	99.0	30.8	2.71	8.8		0.300
1000	77	97.4	29.3	2.65	8.7	~	0.707
1250	78	96.3	26.8	2.38	. 8.2		0.173
1600	78	97.4	27.5	2.20	·7.8	~,-	0.583
2000	78	97.2	26.3	1.93	7.3	-,-	0.200
2500	84	99.7	22.4	1.64	6.6	-,-	0.200
3150	86	99.5	19.5	1.51	6.2	-,-	0.458
4000	87	99.5	18.2	1.36	5.7		0.412
5000	86	96.8	· 16.5	1.21	5.2	. -	0.755

STL = Sound Transmission Loss, dB

L1 = Source Room Level, dB

L2 = Receiving Room Level, dB

T = Reverberation Time, seconds

Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.





Acoustical Testing Laboratory





Not for release or reproduction

Sound Transmission Loss Test Data

Per: ASTM E 90 - 02 / ASTM E 413 - 87

Page 4 of 4

No. of test report: NGC5004002

Test Date: 2/25/2004


Size: 17.8 m²

Temperature [°C]: 19.8

Sound Transmission Class STC = 73 dE

	-	
Frequency	STL	ASTL
[Hz]	[dB]	
100	51	1.249
125	50	1.536
160	54	0.616·
200	58	0.548
250	62	0.574
315	67	0.548
400	71	0.300
. 500	71	0.686
630	71	0.400
800	77	0.300
- 1000	77	0.707
1250	78	0.173
1600	78	0.583
2000	78	0.200
2500	84	0.200
3150	86	0.458
4000	87	0.412
5000	86	0.755
	The second liverage of	

 Due to high insulating value of specimen, background levels limit results at these frequencies.



STL = Sound Transmission Loss, dB

Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's test reports in no way constitutes or implies product certification, approval, or endorsement by this laboratory.

