

K-Standard

Toilet/Shower Partition Specifications

5214 KERMAC TOILET AND SHOWER CUBICLE PARTITIONS

1 GENERAL

Documents

1.2 DOCUMENTS

Documents referred to in this section are:

AS/NZS 1860 Particleboard flooring, 1860.1: Specifications

Documents listed above and cited in the clauses that follow are part of this specification. However, this specification takes precedence in the event of it being at variance with the cited document.

1.3 MANUFACTURER'S DOCUMENTS

Manufacturer's and supplier's documents relating to work in this section are:

KerMac Industries Cubicle and Wall System Manual, tel (09) 2731524

Requirements

1.4 SAMPLES

Submit on request samples of panels and componentry for approval of colour and finishes.

1.5 QUALIFICATIONS

Workers to be experienced, competent and familiar with the materials and techniques specified. Installation to be carried out by workers authorised by the screen manufacturer.

Warranties

1.6 WARRANTY

Warrant this work under normal environmental and use conditions against failure of materials and execution

Warranty period: 2 years

Refer to the PRELIMINARIES AND GENERAL section for the required form of warranty agreement and details of when completed warranty must be submitted.

2. PRODUCTS

Materials

2.1 PARTITIONING SYSTEM

Proprietary partitioning system.

System manufacturer: KerMac Industries

System: K-Standard

www.kermac.co.nz

2.2 CHANNELS, RAILS AND BRACKETS

Extruded aluminium alloy 6063 with exposed face anodic coated.

2.3 PANELS, PARTICLE BOARD

To AS/NZS 1860.1, 18 mm thick with laminate fully glued both sides.

2.4 PANELS, PLYWOOD

Resin bonded 17.5 mm plywood with laminate fully glued both sides.

2.5 DOORS

To match the rigid panels complete with aluminium channel 4 sides.

Components

2.6 HINGES

To match the aluminium section in size, 3 hinges per door.

Type: Butt

Finish: stainless steel

2.7 PEDESTALS

Metal standard with flanged top and bottom to screw fix to panel and floor.

Type: Alloy

3. EXECUTION

Conditions

3.1 HANDLE AND STORE

Handle and store tracks, studs, panels and accessories to avoid damage. Keep dry in transit, store clear of and on a level floor and cover for protection.

3.2 SUBSTRATE

Ensure substrate plumb, level and in true alignment.

3.3 PROTECT

Protect adjoining areas, surfaces and finish from damage.

Application

3.4 INSTALL SCREENS

Carry out the fixing, erection and fitting to finish rigid, plumb, true to line and face and square, to the screen manufacturer's requirements.

3.5 INSTALL COMPONENTS

Hang doors and fit hardware to the screen manufacturer's requirements.

Completion

3.6 REPLACE

Replace damaged or marked elements

3.7 LEAVE

Leave work with parts fully and freely working and to the standard required by following procedures.

3.8 REMOVE

Remove debris, unused materials and elements from the site.

4. SCHEDULES:

4.1 PARTITIONING SYSTEM

Manufacturer: KerMac Industries

Brand: K-Standard

4.2

CHANNELS, RAILS AND BRACKETS

Colour: natural silver anodized

4.3

Laminate: TBA

Finish: to be selected

PANELS, PLYWOOD

Laminate : to be selected

4.4 HARDWARE

Indicator bolt and keeper: standard KerMac stainless finish

Hat and coat hooks: standard KerMac Stainless finish